SAUDI ARABIA PAGE - 1

Tel: 966 12 684 8046

966 12 684 8959 966 12 640 5622

AFS OEJDYKYX http://www.sans.com.sa

Fax:

E-mail: aim@sans.com.sa

KINGDOM OF SAUDI ARABIA

GENERAL AUTHORITY OF CIVIL AVIATION SAUDI AIR NAVIGATION SERVICES AERONAUTICAL INFORMATION MANAGEMENT P. O. BOX 929, JEDDAH - 21421 AIP SUP AIP SUP 05/24 13 MAR 2024

Civilian Apron (stands 4,5,and 6): APRON BUILDING (Earthwork, Excavation, Backfilling Levelling & Compaction Works).

AREA (Civilian Apron)

1 INTRODUCTION

- 1.1. This AIP Supplement aims to notify operators regarding the Earthwork, Excavation, Backfilling Levelling & Compaction Works for civilian apron stands (4,5,6).
- 1.2. The working area related to apron building work is provided in attachment.
- 1.3. This AIP Supplement will remain in force until the end of scope of work and civilian apron stands activation.

2 PURPOSE

- 2.1. Inform pilots and operators about the duration and timeline of working Area and closure of civilian apron stands (4,5,6) in Taif Airport.
- 2.2. Disseminate the temporary operating procedures.
- 2.3. Detailed the affected areas in the airport.
- 2.4. Detail the safety control measures.

3 PHASES OF WORK

- 3.1. Closure a part of the civilian apron.
- 3.2. Construct a temporary fence around working area (height: 2.40 m).
- 3.3. Start Earthwork, Excavation, Backfilling Levelling & Compaction Works.

4 TIMELINE, OPERATIONAL PROCEDURES AND SAFETY MEASURES

Area	Duration	Start–End Dates	Construction activities	Safety measures	
civilian apron stands (4,5,6)	120 days	15-MAR-24 TO 13-JUL-24	-Installation of safety barriers &security fence. - the location shall be checked to ascertain the type of soil to be excavated and appropriate equipment shall be deployed. - remove the existing apron asphalt and excavation for foundations of stee Istructures - Compact the existing subgrade - New rigid pavement Portland cement concrete as per approved drawings. - Spray the anti-termite chemical then provide the polythene sheet, and placement of portland cement concrete 38cm for rigid pavement to the required level.	- Barrier located at the boundary of the constructionareas to avoid any uncontrolled access Steady lights on the barrier that isolates the working area.	

5 PRECAUTIONS

- 5.1. During all phases of the project, pilots must be careful of construction area
- 5.2. During construction pilots should pay attention when taxing near the work area
- 5.3. Pilots must carefully check AIP amendments and NOTAMS for any updates
- 5.4. Presence of construction workers, materials, and equipment in work area.
- 5.5. During all phases of the project TWY "B East" will be limited for code C aircrafts.

6 TEMPORARY FENCE & EQUIPMENT

A temporary fences and equipment cranes will be used for developing the area of the work indicated with the following coordinates. Please note that the mentioned coordinates are not the exact location of the equipment but represent the equipment movement zones. However, pilots must pay attention to the equipment all over the working area

Obstacles during work at civilian apron stands (4,5,6).										
Location	LATITUDE	LONGITUDE	Height AGL	Height AGL	Height AMSL	Height AMSL	Work Start	Work Finish		
			Meter	Feet	Meter	Feet				
1	21°2856.24 N	040°3313.97 E	23	75.459	1453.38	4767.06	15-MAR-24	13-JUL-24		
2	21°2856.99 N	040°3316.96 E	23	75.459	1452.51	4765.45	15-MAR-24	13-JUL-24		
3	21°2854.16 N	040°3317.80 E	23	75.459	1452.81	4766.44	15-MAR-24	13-JUL-24		
4	21°2853.40 N	040°3314.77 E	23	75.459	1453.45	4768.54	15-MAR-24	13-JUL-24		

7 INQUIRIES

For any inquiries on the airside development project at Taif Airport, please contact:

 Name: Abdulrahman .S. Alhashmi
 Function: Taif International Airport director
 Email: aalhashmi@cluster2airports.sa

Tel: +966 55 554 3440

2.

Name: Mashari .A. Alhakami Function: Operation supervisor

Email: mealhakami@cluster2airports.sa

Tel: +966 55 355 5265

THIS PAGE INTENTIONALLY LEFT BLANK

SAUDI ARABIA

